

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/RD/WORK_INDENT24212

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Improvements to roads and drains in Kodigehalli and extension areas in ward no. 8, kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				N VENKATA REDDY	
				In Figures	In Words
1	50.63	Removing B.S slab of drain and stacking	sqm	63.72	Rupees Sixty Three and Seventy Two Paise Only
2	402.9	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.50m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications	cum	83.16	Rupees Eighty Three and Sixteen Paise Only
3	58.2	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement 220kgs,with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @0.465 cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation including cost all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5236.92	Rupees Five Thousand Two Hundred Thirty Six and Ninety Two Paise Only
4	160.8	Providing laying plain/ reinforced cement concrete for Box Drain walls of thickness 10cm to 20cm including centering shuttering for work etc.complete as per approved drawing and design MORTH specification No.1500, 1700, 2200. M20 Grade using Concrete mixer	cum	6931.44	Rupees Six Thousand Nine Hundred Thirty One and Forty Four Paise Only
5	9.6	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @0.43 cum with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed -2008, machine mixed concrete laid in layers not exceeding 15cms thick well compacted in foundation, plinth and cills including cost of all materials, labour, HOM of machinery, curing complete as per specifications	sqm	5991.84	Rupees Five Thousand Nine Hundred Ninety One and Eighty Four Paise Only
6	10.3	Providing T.M.T. steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	MT	34570.0	Rupees Thirty Four Thousand Five Hundred Seventy Only
7	294	Providing and fixing RCC 1:2:4 Precast slab for covering using 20mm and Downsize granite jelly as per design including necessary centering, forming, Curing and finishing with CM 1:3 etc complete 10mm thick	sqm	1836.0	Rupees One Thousand Eight Hundred Thirty Six Only
8	44	Providing and fixing RCC 1:2:4 Precast slab for covering using 20mm and Downsize granite jelly as per design including necessary centering, forming, Curing and finishing with CM 1:3 etc complete 250mm thick	sqm	5111.0	Rupees Five Thousand One Hundred Eleven Only
9	652.9	Lead for disposal of debris shall be payable at carriage rates by mechanical means including loading and unloading From 13.30 Kms	cum	123.2	Rupees One Hundred Twenty Three and Twenty Paise Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92


19/04